

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE

13th March, 2024

CORRIGENDUM

EO/A/HOSTEL/WKS-145/23-24

Name of Work : Providing and applying waterproofing chemical treatment to external walls of Hostel No. 18.

This is with reference to above-mentioned work in which there is a change in description of Serial Item No. 10 of schedule of work. Details as mentioned below:

Previous description of work in item No. 10	Amendment in description of work in item No. 10
ITEM No. 10) Providing and applying one or more coat of Dr. Fixit Raincoat Universal Base Coat over plaster, masonry or RCC surface of any height including scaffolding and without any dilution at a spreading rate of 3.5 -4.0 sq mtr per litre to achieve about 120-150 microns DFT as per manufacturer specification including preparing the surface by thoroughly cleaning laitance, loose material, oil, grease and other foreign matter with wire brush and vacuum cleaning, filling the cracks using appropriate exterior putty, covering the floor and wall, window glass with plastic sheet during work and cleaning after work etc. all complete as directed. (For vertical surface).	ITEM No. 10) Providing and applying one or more coat of Dr. Fixit Raincoat Universal Base Coat over plaster, masonry or RCC surface of any height without any dilution at a spreading rate of 3.5 -4.0 sq mtr per litre to achieve about 120-150 microns DFT as per manufacturer specification including preparing the surface by thoroughly cleaning laitance, loose material, oil, grease and other foreign matter with wire brush and vacuum cleaning, filling the cracks using appropriate exterior putty, covering the floor and wall, window glass with plastic sheet during work and cleaning after work etc. all complete as directed. (For vertical surface).

R. Shekhar
13/03/2024

Superintending Engineer (I/C)